




# PJM Interconnection Queue Progress

Donnie Bielak

Director, Interconnection Planning

October 28, 2025

- PJM's reformed queue process began in December 2023 with 171 GW of backlog projects to process through two Transition Cycles and an Expedited Process
- PJM has kept Transition Cycle milestone commitments resulting in 63 GW remaining in backlog (63% reduction) through July 2025
- A total of 44 GW are through the study process with interconnection agreements with balance of Transition Cycle backlog agreements to be issued in 2025 and 2026
  - 29 GW of projects with signed agreements since 2015 have since withdrawn
- PJM made significant investments in innovative tools & automation, staffing, and process development to achieve this progress
- PJM is on schedule to begin the normal interconnection cycle process for new resources in early 2026



PJM emphasizes increasing quality while also reducing completion time.

PJM emphasizes adding automation to enrich the full pipeline needed to interconnect generation (not just the interconnection study step).

**Combined Benefit of PJM Automation and Staffing Increases of 100% Has Reduced Processing Time by 60% while Increasing Quality, Allowing PJM To Achieve Queue Reform Goals**

*Interconnection Process*



## Application Submission

## Interconnection Study

## Reinforcement Development

## Final Agreement Negotiation

## Post Agreement

- **Queue Scope** – Preliminary analysis to guide prospecting 2022
- **Queue Point Enhancements** – Retrofit to support Fast Lane and TC1 2023
- **NextGen** – New interconnection customer portal 2025+
- **AI Enhancements** – Deficiency review automation 2025

---

- **PowerGEM TARA** – GenDeliv Enhancements 2024
- **Queue Destination** – Build model, process GenDeliv results, automate cost allocation and reports. 2022

---

- **Queue Destination for TOs** – Expedite result processing and upgrade scoping 2025

---

- **PowerTemplate** – Automation to help draft GIA and other legal documents 2025

---

- **InfraTrack** – Milestone tracking, invoice cost allocation, task tracking 2024

*More details in Appendix I*

## Cost Allocation to Projects in Cycle

- Challenge
  - Complex calculation done manually - error prone and time consuming
- Solution
  - Automated cost allocation calculations for majority of cases

## Transmission Owner Collaboration

- Challenge
  - Manual TO word document per project with risk of conflicting TO reinforcements on different project reports
- Solution
  - Improved user interface links data across multiple TO reinforcements together to avoid conflict

## Project Modeling Details

- Challenge
  - Must manually manage project data changes with risk that changes not always reflected in case
- Solution
  - Queue Destination centralizes all project data and checks cases for correct data

## Post-GIA Project Completion Tracking

- Challenge
  - 50+ tasks tracked manually without consistent approach making it difficult to manage
- Solution
  - InfraTrack added common tracking and better reporting of tasks needing to be completed

Task	Before Automation	After Automation	TC1 Time Savings	TC2 Projected Time Savings
<b>Cost Allocation</b>	1–4 hours per report	Seconds (fully automated)	1500 hours	2500 hours
<b>Report Generation</b>	2–4 hours per report	30 minutes per report	1500 hours	3000 hours
<b>Validation of Upgrades</b>	1–2 days per report	3–6 days per cycle	1000 hours	2000 hours
<b>Case Building</b>	2–4 months	2–4 weeks	700 hours	800 hours

**In 19 months since beginning the Transition Cycles, PJM has relieved the interconnection backlog by 63%, has almost 44 GW of projects ready to construct, and placed over 6 GW of new generation into service**

July 2023	December 2023		July 2025	
FERC Approval	Expedited	26 GW applied	Expedited	0 GW remaining
	Transition Cycle 1	45 GW applied	Transition Cycle 1	17 GW under Phase III study
	Transition Cycle 2	100 GW eligible	Transition Cycle 2* <small>*Includes RRI</small>	46 GW under Phase I study
	<b>Total in Queue</b>	<b>171 GW</b>	<b>Total in Queue</b>	<b>63 GW remaining</b>

Backlog has been reduced significantly (63%) in the past 19 months

Automation and staffing have played a key role in accelerating process while improving quality

PJM is on track to process new applications in early 2026

PJM continues to invest in automation and tools to improve efficiency and quality of the interconnection process



# Appendix I: PJM Tools

## Geographic Interface for Queue Scope

- Queue Scope
  - Inform on locations with available transmission system overhead
  - Visual geographic and tabular interface

The screenshot displays the Queue Scope web application interface. At the top, there are filters for Case (2024 AG1 Queue Case (Summer peak)), Transmission owner (COMED), Voltage level (All), and Operating mode (Injection). A 'Select Buses to Study' dialog box is open, showing a list of buses with their names and pre-loading percentages. Below the map, the 'Evaluation Results' section shows a table of transmission facilities with columns for Contingency Type, Available (MW), DFax, Impact (MW), Pre-Loading (%), and Post-Loading (%).


Transmission Facility	Contingency Type	Available (MW)	DFax	Impact (MW)	Pre-Loading (%)	Post-Loading (%)
314203 6MACKEYS 230 314637 6EDENTON 230 1	Single	0	0.06235	0.00	152.19	152.19
314616 6TRVBRDG 230 933990 AD1-023 TAP 230 1	Tower	0	0.06235	0.00	151.19	151.19
314638 6ELIZ CT 230 314647 6SHAWBRO 230 1	Single	0	0.13036	0.00	116.57	116.57
941850 AE2-190 TAP 230 314037 6GAINSVL 230 1	Single	0	0.09478	0.00	110.41	110.41
314267 3CHASCTY2 115 314681 3CHASCTY 115 Z1	Tower	0	0.09474	0.00	102.72	102.72
314296 6PENNINGAN 230 314415 6WALR209 230 1	Single	36	0.09474	0.00	91.87	91.87

## Queue Point & NextGen

- Queue Point Enhancements to support Fast Lane and TC1
- NextGen to support Cycle 1 applications and TC2 DPI and further forward
- Future
  - AI to automatically review applications
  - Find deficiency in Site Control, acreage requirements, alignment between submission and engineering drawings, etc.
  - Anticipated by January 2026

## Section of NextGen Interconnection Application

**Direct Connection**  
 Example depiction of a generator interconnecting to an existing Transmission Owner substation, which needs to be expanded to accommodate the interconnection.



**Legend:**

- Project Developer Interconnection Facility
- Transmission Owner Interconnection Facility
- Network Upgrades
- ◆ Point of Interconnection
- ◆ Point of Change in Ownership

**Form Fields:**

POI substation name \*  Substation PSS/e bus number

Interconnection voltage \*  KV

**POI Location**

Queue Scope's tabular and geospatial applications with secure or secure + CEII data requires access approval in Account Manager. Follow the steps in the Queue Scope User Guide to set up or update your account in Account Manager for access.

[View Queue Scope Tool](#)

Latitude \*  Longitude \*


Must be between 34 and 44 N Must be between -92 and -72 W

Address

City  State  County  Zip/Postal code

## Queue Destination POI Tool

- POI tool built into Queue Destination
  - Automatically add modeling
  - Point engineers to specific trouble spots.
- Modeling automation
  - Automatically bridge modeling data from NextGen into POI tool
  - Anticipated by December 2025



The screenshot displays the Queue Destination POI Tool interface with the following sections:

- POI Review:**
  - POI Review Status: Data Validated
  - Transmission Level POI (unchecked = Distribution)
  - Special Manual Modeling Required
  - Comments: POI modeling corrections may be needed. Confirming with Dominion
- Injection MW Override:**
  - Analysis: Fuel Type, MFO, MWC, MWE, Chrg MW, Gen Class, Effective, Terminate, Comments
  - Buttons: Add, Remove
- Injection History (from Planning DB):**

Timestamp	Old MFO	New MFO	Old MWC	New MWC	Old MWE	New MWE
7/11/2024 1:52:40 PM	880	833	267.5	253.2	880	833
- Shared POI:**
  - CVOW Harpers 230 kV - Dominion
  - Map Shared POI
- Shared POIs:**

Project	Project Status	Project Name	View
AF1-123	Active	Oceana 230 kV	
AF1-124	Active	Oceana 230 kV	
AF1-125	Active	Oceana 230 kV	
- Interconnection Topology Definitions:**
  - Connect to 314963 GOCEANA 230.0 [LF]
  - Connect to 314909 FENTRESS 500.0 [SC]
  - Buttons: Add, Remove
- POI Definition for 'Connect to 314963 GOCEANA 230.0 [LF]':**
  - Domain: Load Flow
  - Selected Bus: 314963 GOCEANA 230.0
  - Eccentric Topology Change: Harpers and CVOW OSW
  - Buttons: Add, Edit, Clear
- Reserved Buses:**

Bus #	Type
944580	Tap
944581	Capacity
944582	Energy
944583	Future Use
944584	Future Use
- Generators Modeled in POI Build:**

Modeled	Bus #	Gen Id	Gen Class	Status	PMax	PMin	Owner

- Partnered with PowerGEM to create recently enhanced GenDeliv test
- Queue Destination provides interface for PJM and TO engineers to review results

## Queue Destination Flowgate Review

The screenshot displays the Queue Destination Flowgate Review interface. At the top, there are navigation tabs for various analysis types, with 'Load Flow Analysis' selected. Below this is a filter bar and a table of flowgates. The table includes columns for Area, Facility, Contingency, Ctg Type, Priority, Rating, Full Contrib MW, Full Contrib %, DFAX, Pre-Prj % Loading, Post-Prj % Loading, Final AC % Loading, Final DC MW, Review Status, and Sensitivity Flowgate Mapping. A detailed view for flowgate 'GCHSTF B 230.0 to 6BASIN 230.0' is shown, including its rating (1 - Reportable) and a 'PJM Flowgate Comments' section. Below the detailed view is a summary table with columns for 'Init Post Ctg Flow', '50/50 Flows (MW)', 'Adder Flows (DC MW)', and 'Final AC & DC Solution'. The summary table shows values for Gen, MTX, CLTF, LTF, Adder Impact, External Queue, DC, and AC. At the bottom, there is a large table with columns for Bus #, Bus Name, Area, Project Status, Pmin, Pmax, Pgen, Headroom, EEFORD, New, Capacity/Energy, DFAX, Commercial Probability, Cumulative Availability, GenDeliv MW Impact, and Flag.

- Partially automated short circuit POI tool
- Automated ingestion of short circuit results (expected June)
- Stability automation on road map for 2026+

- New Transmission Owner UI to aid in coordinated development of upgrades
- Database of previous upgrades that TOs can draw upon
- Automated cost allocation

## Queue Destination Transmission Owner Interface

Queue Destination for AEP Queue Projects Load Flow Analysis Upgrades Admin Cycle TC1: PH2

Filter **Max Facility Overloads**

Facility	Max Loading (MVA)	# Flowgates
05DUMONT 765.0 kV to WILTON ; 765.0 kV ckt 1	4,160.5 MVA	2
05OLIVE 345.0 kV to GREENACRE; T 345.0 kV ckt 1	1,376.8 MVA	5

Reliability Network Upgrades Flowgates Debug

**Need to reinforce WILTON - 765.0 kV to 05DUMONT 765.0 kV ckt 1 RateB LL (case rating is 4105 MVA) to be > 4,160.5 MVA**

RTEP ID	TO ID	Title	RateB LL
n6600	AEP10001a	Replace Dumont Circuit Breaker B1	5001 MVA
n6860	CE_NUN_L11215	Wilton Upgrade existing Current Transformers	4460 MVA
n5252	CE_NUN_L11215_1	Mitigate the sag on L11215	4105 MVA

Create New Reliability Network Upgrade

Overview Flowgates Addressed Modeling Queue Projects Debug Save

RTEP ID: n6600 Trans Owner Ref Code: AEP10001a

Legal Entity: American Electric Power Trans Owner: AEP

Title: Replace Dumont Circuit Breaker B1

Description: Replace Dumont Circuit Breaker B1 [Breaker (3000A) Non oil - Dumont]

Time Estimate: 18 to 24 months

Cost Estimate:  Use Detailed Cost Estimate  Simple Cost Estimate \$3,900,000

Next Limiting Equipment:

Prerequisite: (No Prerequisite)

Needed by TC1: Yes

Trans Owner Review:  Invalid Reinforcement

Word Doc: undefinedfacility...y\10265\_n6600.doc Ready for PJM:

Facility Study: Comments:


Download Replace

- Separate sensitivity run performed and results displayed alongside basecase results
- Provides solution verification and cost allocation of backbone solutions.

Area	Facility	Contingency	Ctg Type	Priority	Rating	Full Contrib MW	Full Contrib %	DFAX	Pre-Pj % Loading	Post-Pj % Loading	Final AC % Loading	Final DC MW	Review Status	Sensitivity Flowgate Mapping
DVP	6CHESTF B 230.0 - 6BASIN 230.0 ckt 1	DVP_P4-2: 562T563_SRT-S	Breaker	1 - Reportable	812.0 MVA	45.1 MW	5.55 %	0.05413	128.66 %	133.39 %	151.31 %	1,234.87 MW	pjm TO 0/5	1139.84 MVA(88.79 MVA) [140.37% (10.93)%] ↑
DVP	6CHESTF B 230.0 - 6BASIN 230.0 ckt 1	DVP_P1-2: LN 563_SRT-S-1	Single	1 - Reportable	663.6 MVA	15.3 MW	2.31 %	0.06042	128.49 %	130.31 %	139.14 %	924.38 MW	pjm TO 0/5	944.00 MVA(-20.61 MVA) [142.25% (-3.10)%] ↓
DVP	6ELMONT 230.0 - 8ELMONT 500.0 ckt 1	DVP_P4-2: H2T557_SRT-S	Breaker	1 - Reportable	1,065.0 MVA	117.7 MW	11.06 %	0.14135	111.34 %	117.49 %	135.90 %	1,449.22 MW	pjm TO 1/2	1819.58 MVA(-372.29 MVA) [170.85% (-34.96)%] ↓
DVP	8MDLTHAN 500.0 - 8NO ANNA 500.0 ckt 1	DVP_P7-1: ELMONT-LADYSMITH_5	Tower	1 - Reportable	3,940.0 MVA	237.6 MW	6.03 %	0.28528	106.77 %	107.72 %	110.39 %	4,345.08 MW	pjm TO 2/4	+
DVP	8MDLTHAN 500.0 - 8NO ANNA 500.0 ckt 1	DVP_P4-2: 557T574_SRT-S	Breaker	1 - Reportable	3,940.0 MVA	239.9 MW	6.09 %	0.28800	101.98 %	103.13 %	106.60 %	4,186.37 MW	pjm TO 2/4	4859.25 MVA(-659.22 MVA) [123.33% (-16.73)%] ↓


*Queue Destination Flowgate with Sensitivity Run*

- Fully automated cycle report
- Fully automated individualized project report
- Quickly regenerate reports




*Automatically Generated Report*

- New tool PowerTemplate to help draft GIA documents (expected April)
- Plan to use tool to draft other documents needed as part of interconnection process: NUCRA, CSA, WMPA
- Will enable PJM to streamline final agreement phase



## InfraTrack tool to help with process after GIA is signed

- Milestone Tracking
- Invoice Cost Allocation Automation
- Tracking for PJM internal processes
  - To manage the agreement (necessary study, interim deliverability, milestone extension, agreement to amend, scope change, suspension, breach)
  - To allow energization (EMS modeling, telemetry, PMUs, test energy, release to dispatch)



The screenshot displays the InfraTrack web application interface. At the top, it shows 'InfraTrack Dashboards' and a 'Goto Queue Project' button. The main header identifies the project as 'AB2-136 Egypt Road Solar' with sub-headers 'Egypt Road Solar, LLC' and 'DPL'. The location is 'MACELANE / 34.5 KV / MACESP' and the contact is 'CE: Art Wolfe'. A navigation menu includes 'Overview', 'Milestones and Key Dates', 'Meeting Minutes', 'PJM Tasks', 'System Reinforcements', 'Invoices', 'Necessary and As Built Studies', and 'eDART Outa'. The left sidebar lists project milestones: 'Project Kickoff', 'EMS Modeling Telemetry', 'Voltage Schedule', 'MDM Ticket and Markets Setup', 'Solar/Wind Forecast Worksheet', 'PMU', 'Pre-Test Energy Checklist', 'Post-Test Energy Checklist', and 'Project Closeout'. Below these are buttons for 'New Task From Template' and 'New Custom Task'. The main content area shows a 'Voltage Schedule' task with 'Applicable Key Dates' for 'Test Energy' on 'Sep 29 2025'. A 'Subtasks' section contains two items: 'TO specifies voltage schedule during design phase. Send to Developer and voltageschedules@pjm.com' (marked 'Complete') and 'Verify eDART ticket completed for voltage schedule' (marked 'Unstarted'). Each subtask includes fields for Status, Owner (Construction Engineer), Due date, and Reminder Starting date.